

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18557/CALL-2

APPROVED SCHEDULE - B

EE/TP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

**Improvements to Roads and Drains of Ambedkar Colony Main Road Dasarahalli in Ward No.6
Byatarayanapura Sub Division**

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				V CHANDRAPPA		
				In Figures		In Words
1	445.89	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16	Cum	268.17	119574.32	Rupees Two Hundred Sixty Eight and Seventeen Paise Only
2	85.38	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	4715.66	402623.05	Rupees Four Thousand Seven Hundred Fifteen and Sixty Six Paise Only
3	17.55	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2015-16	cum	3845.85	67494.67	Rupees Three Thousand Eight Hundred Forty Five and Eighty Five Paise Only
4	14.63	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2015-16	Sqm	4561.98	66741.77	Rupees Four Thousand Five Hundred Sixty One and Ninety Eight Paise Only
5	1387.05	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2015-16	Sqm	251.1	348288.26	Rupees Two Hundred Fifty One and Ten Paise Only
6	5.85	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16	cum	5107.37	29878.11	Rupees Five Thousand One Hundred Seven and Thirty Seven Paise Only
7	32.5	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2015-16	Sqm	92.4	3003.00	Rupees Ninety Two and Forty Paise Only


Executive Engineer
 Byatarayanapura Division
 BBMP, Bangalore-92

30/4/16.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				V CHANDRAPPA		
				In Figures		In Words
8	164.07	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2015-16	Cum	5764.25	945740.50	Rupees Five Thousand Seven Hundred Sixty Four and Twenty Five Paise Only
9	12.31	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16	Qtl	64919.39	799157.69	Rupees Sixty Four Thousand Nine Hundred Nineteen and Thirty Nine Paise Only
10	504	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1726.7	870256.80	Rupees One Thousand Seven Hundred Twenty Six and Seventy Paise Only
11	445.89	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	62.61	27917.17	Rupees Sixty Two and Sixty One Paise Only
					3680675.34	


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
30/4/16


30/04